

NAME OF THE WORK – ESTIMATE FOR KOTA STONE SLAB FLOORING AND SKIRTING FOR HOSTEL C(G+2) AT SAINIK SCHOOL PUNGLWA

<u>SI No</u>	<u>PARTICLUARS</u>	<u>UNIT</u>	<u>QTY</u>	<u>RATE</u>	<u>AMOUNT</u>
1	Dismantling of existing Cemented flooring and Skirting raking out joints and cleaning the surface including disposal of rubbish to the dumping ground within 50m lead	Sq M	2778.75		
2	Kota Stone Slab flooring over 25mm (average) thick base laid over and jointed with Grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of 1:4 91 cement : 4 coarse sand)	Sq M	2649.75		
3	Kota Stone Slab skirting laid on 12mm (average) thick cement mortar 1:3 and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete	Sq M	201		
TOTAL					

Total amount in Words Rs _____/-

(_____)

inclusive of all taxes, labour charges and transportation charges etc